



# मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्र.२८१९२८२८

**बांधकाम / विद्युत विभाग**

जा.क्र. मनपा/साबां/ 31

/2024-25

दि. 29/07/2024

प्रति,

जनसंपर्क अधिकारी

जनसंपर्क विभाग

मिरा भाईंदर महानगरपालिका

**विषय :-** जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

मिरा-भाईंदर महानगरपालिका हद्दीतील स्व.प्रमोद महाजन कला दालन अंतर्गत सजावट करणे बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload करण्यात यावीत.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईंदर महानगरपालिका

6



## मिरा भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईंदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्र.२८१९२८२८

**बांधकाम / विद्युत विभाग**



जा.क्र. मनपा/साबां/ 31

/2024-25

दि. 29/07/2024

प्रति,

सिस्टीम मॅनेजर

माहिती तंत्रज्ञान विभाग

मिरा भाईंदर महानगरपालिका

**विषय :-** जाहीर सुचना महानगरपालिकेच्या अधिकृत संकेतस्थळावर प्रसिध्द करणेबाबत.

महोदय,

मिरा-भाईंदर महानगरपालिका हद्दीतील स्व.प्रमोद महाजन कला दालन अंतर्गत सजावट करणे बाबींसाठी ऑनलाईन स्पर्धात्मक दर मागविणे कामी सोबत जोडण्यात आलेली दरपत्रके महानगरपालिकेच्या अधिकृत संकेत स्थळावर प्रसिध्द / upload करण्यात यावीत.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईंदर महानगरपालिका

४



## मिरा भाईदर महानगरपालिका

स्व. इंदिरा गांधी भवन, मुख्य कार्यालय, छत्रपती शिवाजी महाराज मार्ग,  
भाईदर (प.), ता.ठाणे-४०११०१ दुरध्वनी क्र.२८१९२८२८  
बांधकाम / विद्युत विभाग

जा.क्र. मनपा/साबां/३१ /2024-25  
दि. 29/07/2024

### // जाहिर नोटीस //

मिरा-भाईदर महानगरपालिका हद्दीतील स्व.प्रमोद महाजन कला दालन अंतर्गत सजावट करणे. कामी चालु जिल्हा दरसुचीमध्ये दर उपलब्ध नसल्यामुळे खुल्या बाजारातून दरपत्रक मागविण्यात येत आहे.

सदर कामाकरिता दि.०६/०८/२०२४ रोजी संध्या ४.०० वाजेपर्यंत मिरा भाईदर महानगरपालिका, मुख्य कार्यालय, बांधकाम विभाग, ४ था मजला येथे स्वारस्य असलेल्या कंत्राटदाराने सोबत जोडलेल्या दरपत्रकातील बाबींकरीता दर भरून देण्यात यावेत.

(नितिन मुकणे)

कार्यकारी अभियंता (साबां/वि)

मिरा भाईदर महानगरपालिका



**MIRA BHAINDAR MUNICIPAL CORPORATION**  
**PWD / Electrical Department**  
**Indira Gandhi Bhavan, Chhatrapati Shivaji Maharaj Marg,**  
**Bhaindar (W) 401101,**  
**Tal. Dist – Thane, Ph. 28192828**

**// RATE FORM //**

**Name of Work :- PROPOSED CONSTRUCTION OF PRAMOD MAHAJAN ART GALLERY**  
**Name and address of Contractor :-**

**B-2 FORM**

| Sr. No. | Description  | Qty  | UNIT | RATE |
|---------|--|------|------|------|
| 1       | Wooden floor tiles (including skirting)<br>Providing & laying Hardwood flooring (strip format) with standard specifications, Board constructed with 3 layers, Top layer of 3 to 6 mm thk veneer, Core material of high density fiber board, and balancing layer, Wood species of as per selection (oak, Walnutm Teak, Ash and other exotic species). The surface to be pre- finished with UV hardner acrylic hardner, free of formaldehyde and solvents. Finish of Top layer to be Matt or Satin or brushed having resistance to house hold chemicals & stains and not to change colour.<br>RA<br>Spec. As directed by Engineer-In-Charge. | 1.00 | SMT  |      |
| 2       | Providing and fixing Counter table L Shape (6.05m x 0.60 m +2.05 X 0.60 m) - 0.60 m width for main counter made of 18 mm thk Marine plywood including table top, drawers, shutters main support, internal supports, table top to have frosted glass partition fixed on wooden supports, all external surfaces finished with approved laminate of 1.0 mm thk & all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete. loacation- audio visual operation room Spec. As directed by Engineer-In-Charge. (Face Area To be Measured)<br>RA                    | 1.00 | SMT  |      |

|   |   |      |     |  |
|---|---|------|-----|--|
| 3 | <p>Providing and fixing Concierge table (3.30 m x 0.75 m + 3.60 m x 0.75 m) - 0.60 m width for main counter made of 18 mm thk marine plywood including table top, with drawers, shutters main support, internal supports, table top to have frosted glass partition fixed on wooden supports, all external surfaces finished with approved laminate of 1.0 mm thk &amp; all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete. location-atrium</p> <p>MR<br/>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | SMT |  |
| 4 | <p>Providing and fixing Cabin table (2.1 m x 0.90 m) made of 18 mm thk Marine plywood including table top, with four drawers, two shutters main support, internal supports, all external surfaces finished with approved laminate of 1.0 mm thk &amp; all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 5 | <p>Providing and fixing Cabin table (1.5 m x .75m) made of 18 mm thk plywood including table top, Side credenza with two drawers, two shutters main support, internal supports, all external surfaces finished with approved laminate of 1.0 mm thk &amp; all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 6 | <p>Providing and fixing Librarian table (1.8m x .75m) made of 18 mm thk plywood including table top, Side credenza with two drawers, two shutters main support, internal supports, all external surfaces finished with approved laminate of 1.0 mm thk &amp; all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.</p> <p>Spec. As directed by Engineer-In-Charge.<br/>RA</p>  | 1.00 | NOS |  |

|    |   |      |     |  |
|----|---|------|-----|--|
|    | Spec. As directed by Engineer-In-Charge.  |      |     |  |
| 7  | <p>Providing and fixing Issue Counter table (3.05 m x 0.75m) - 0.60 m width for main counter made of 18 mm thk plywood including table top, Side credenza with two drawers, two shutters main support, internal supports, table top to have frosted glass partition fixed on wooden supports, all external surfaces finished with approved laminate of 1.0 mm thk &amp; all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete. Location- Library area<br/>RA<br/>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | SMT |  |
| 8  | <p>Providing and fixing Studio table (3.05 m x 0.90m) made of 18 mm thk plywood including table top, Side credenza with two drawers, two shutters main support, internal supports, all external surfaces finished with approved laminate of 1.0 mm thk &amp; all internal supports finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.<br/>RA<br/>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | SMT |  |
| 9  | <p>Providing &amp; Supplying Rack for Magazines and New Arrivals. (Size-1.2 m x 2.1 m) Location :- Audio library<br/>RA<br/>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | NOS |  |
| 10 | <p>Providing &amp; Supplying Audio Console Rack - (Size- 0.60 m x 1.80 m)<br/>RA<br/>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 11 | <p>Providing &amp; Supplying Slotted Angle Rack with 6-</p>   | 1.00 | SMT |  |

|    |   |      |     |  |
|----|---|------|-----|--|
|    | Shelf Shelving Unit Multipurpose Rack (Black) (72 X 30 X 18 Inch)(22 Gauge Shelf,16 Gauge Angles.<br>RA<br>Spec. As directed by Engineer-In-Charge.   |      |     |  |
| 12 | Providing & Supplying Display Rack made with MR grade Plywood & partly glazed with 10 mm thk toughened glass, 18 mm thk plywood with all external surfaces finished with approved laminate of 1.0 mm thk & all internal surfaces finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.<br>RA<br>Spec. As directed by Engineer-In-Charge. | 1.00 | SMT |  |
| 13 | Providing and fixing Storage made of 18 mm thk plywood with all external surfaces finished with approved laminate of 1.0 mm thk & all internal surfaces finished with white/offwhite laminate 0.8 mm thk. All wooden surfaces finished with melamine polish. etc complete.<br>RA<br>Spec. As directed by Engineer-In-Charge.  | 1.00 | SMT |  |
| 14 | Providing and fixing Free Standing Pedestal (Size:- 0.60 m x .060 m x .90 m) for Exhibition area<br>RA<br>Spec. As directed by Engineer-In-Charge.  | 1.00 | NOS |  |
| 15 | Providing and supplying Reading table- Type 01 (size- .075 M x 1.05 M ) - MS frame and made of 18 mm thk plywood including table top all surfaces finished with approved laminate of 1.0 mm thk as shown in the drawings.<br>RA<br>Spec. As directed by Engineer-In-Charge.   | 1.00 | NOS |  |
| 16 | Providing and supplying Reading table-Type 02 ( size- 1.50 M x 1.05 M ) - MS frame and made of 18 mm thk plywood including table top all surfaces finished with approved laminate of 1.0 mm thk as shown in the drawings.<br>RA<br>Spec. As directed by Engineer-In-Charge.   | 1.00 | NOS |  |

|    |   |      |     |  |
|----|---|------|-----|--|
| 17 | <p>Providing and supplying Book rack straight with white laminate finish inside and exterior designer laminate finish and as shown in the drawings.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | SMT |  |
| 18 | <p>Providing and fixing Podium with acrylic finish</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | SMT |  |
| 19 | <p>Providing and supplying Cafe table ( Square shape ) - with laminate finish.(table size -out of 0.90 m x 0.90 m) All wooden surfaces finished with melamine polish with moulding finish.location :-Kitchen &amp; Cafe</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | NOS |  |
| 20 | <p>Providing and supplying standard Bench seating ( size -out of 3.00m x 0.60 m) . as shown in the drawings.location :-Kitchen &amp; Cafe</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 21 | <p>Providing and supplying standard High bench seating ( size - out of 11.30 m x 0.60 m) . as shown in the drawings.location :-Kitchen &amp; Cafe</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | SMT |  |
| 22 | <p>Providing and supplying Center table - type 01 Table Top with Toughened Glass &amp; Metal Legs with natural wooden polish</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | NOS |  |

|    |   |      |     |  |
|----|---|------|-----|--|
| 23 | <p>Providing and supplying Center table - ( Square / Round shape ) - with laminate finish.(table size -out of 1.20 m x 1.20 m) All wooden surfaces finished with melamine polish with moulding finish.</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 24 | <p>Providing and supplying Corner table Top with Toughened Glass &amp; Metal Legs with natural wooden polish</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 25 | <p>Providing and fixing Metal body powder coated Cupboards ( Size :- 0.90m X 0.50 m ) with required Locking arrangements &amp; adustable shelves. Make Godrej / Ruby Safe or equivalent .</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | SMT |  |
| 26 | <p>Providing and fixing Luggage Racks (Size :-1.2 mX .45m ) made of 19mm thick ply shutters , finished with approved Veneer on all outer faces complete as per drawings and directions. Cost includes provision of approved hinges, door magnets, handles, etc. as per drawings and specifications.</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | SMT |  |
| 27 | <p>Providing and fixing Dressing Tables (Size :-0.60 m X .45m ) with 2 sets of drawer &amp; shutter below, made of 19mm thick ply shutters , finished with approved Veneer on all outer faces complete as per drawings and directions. Cost includes provision of approved hinges, door magnets, handles, etc. as per drawings and specifications.</p> <p>RA<br/>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | SMT |  |

|    |  |      |     |  |
|----|--|------|-----|--|
| 28 | <p>Providing and supplying Single bed (size- 1.95 m x 0.90 m) - made of 18 mm thk plywood including top all surfaces finished with approved laminate of 1.0 mm thk as shown in the drawings.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 29 | <p>Providing and supplying Side table (size- 0.60 m x 0.45m) with two drawers all surfaces finished with approved laminate of 1.0 mm thk as shown in the drawings. In Suite rooms</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | NOS |  |
| 30 | <p>Providing and fixing Entertainment table for Suite rooms .(TV UNIT)</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | SMT |  |
| 31 | <p>Providing and fixing Full Height Wooden Partitions- Veneer finish made with MR grade Plywood &amp; partly glazed with 10 mm thk toughned glass, nesasary support frames as directed. Finishing complete in all respects with melamine polish to all surafaces &amp; beads, etc. as shown in the drawings.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | SMT |  |
| 32 | <p>Providing and fixing Screen Partition design for audio library .</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | SMT |  |

|    |   |      |     |  |
|----|---|------|-----|--|
| 33 | <p>Providing and fixing Mirror Panelling with 12mm thick commercial BWR plywood / MDF mounted on ply support frame work. Finished with veneer Border frame and melamine polish. Teakwood beading at corners, skirting level and false ceiling level, etc. as per drawing. Basic cost of veneer Rs. 135/- per sq.ft.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>                               | 1.00 | SMT |  |
| 34 | <p>Providing and fixing Acrylic Board panelling on wall</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | SMT |  |
| 35 | <p>Providing and fixing Wall panelling on wall with 12mm thick commercial BWR plywood / MDF mounted on ply support frame work with laser cutting and backlit With LED Finishing includes covering with approved laminate finish the outside of plywood, Teakwood beading at corners, skirting level and false ceiling level, etc. as per drawing.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | SMT |  |
| 36 | <p>Providing and fixing Wall panelling on wall with 12mm thick commercial BWR plywood / MDF mounted on ply support frame work with laser cutting and backlit With LED Finishing includes covering with approved Veneer finish the outside of plywood, Teakwood beading at corners, skirting level and false ceiling level, etc. as per drawing.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | SMT |  |

|    |   |      |     |  |
|----|---|------|-----|--|
| 37 | <p>Providing and fixing Wall slat panelling on wall with 12mm thick commercial BWR plywood on ply support frame work with LED Finishing includes covering with wooden slat of approved on the outside of plywood, Teakwood beading at corners, skirting level and false ceiling level, etc. as per drawing.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p> | 1.00 | SMT |  |
| 38 | <p>Providing and supplying Café Chairs</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | NOS |  |
| 39 | <p>Providing and supplying Standard High Cafe Stools. as shown in the drawings.location:- Library</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 40 | <p>Providing and supplying standard Reading chairs. as shown in the drawings.</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 41 | <p>Providing and supplying standard Audio/ Reading wooden chairs. as shown in the drawings.location:- Library</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>   | 1.00 | NOS |  |
| 42 | <p>Providing and supplying standard Audio Console Stools . as shown in the drawings.location:- Library</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | NOS |  |
| 43 | <p>Providing and supplying standard Studio chairs. as shown in the drawings.location:- Library</p> <p>RA</p> <p>Spec. As directed by Engineer-In-Charge.</p>  | 1.00 | NOS |  |

|    |  |      |     |  |
|----|--|------|-----|--|
| 44 | Providing and fixing Sofa-3 seater with upholstery (office)<br>RA<br>Spec. As directed by Engineer-In-Charge.  | 1.00 | NOS |  |
| 45 | Providing and fixing Sofa-2 seater with upholstery .<br>RA<br>Spec. As directed by Engineer-In-Charge.   | 1.00 | NOS |  |
| 46 | Providing and fixing Sofa-1 seater with upholstery<br>RA<br>Spec. As directed by Engineer-In-Charge.   | 1.00 | NOS |  |
| 47 | Providing & Fixing of Signage using 304 Stainless steel letters for the front & side fascia and 5mm thick acrylic molded letters, for back fascia moulded letters with height 24 inches, with necessary power supplies for connection, including profile LED back lighting<br>RA<br>Spec. As directed by Engineer-In-Charge. | 1.00 | NOS |  |
| 48 | Providing & Fixing Rod (2meter length) & Accessories<br>for Carpet on Steps including brass finish. etc.<br>as per architect's instructions<br><br>RA<br>Spec. As directed by Engineer-In-Charge.  | 1.00 | NOS |  |
| 49 | Providing and fixing Wooden batten ceiling with Veneer finish As per Spec. As directed by Engineer-In-Charge.<br>RA  | 1.00 | SMT |  |

|            |   |      |      |  |
|------------|---|------|------|--|
| 50         | Providing and fixing Designer Fabric ceiling with finish<br>RA<br>Spec. As directed by Engineer-In-Charge.  | 1.00 | SMT  |  |
| 51         | Providing and applying Wallpaper premium Qulaity<br>RA<br>Spec. As directed by Engineer-In-Charge.  | 1.00 | SMT  |  |
| 52         | Providing and Fixing Adjustable Painting stand/Holder as per specification provided by the engineer in charge.  | 1.00 | NOS  |  |
| 53         | Providing and Fixing high tensile strings for hanging Paintings with frame as per specification provided by the engineer in charge.   | 1.00 | RMT  |  |
| ELECTRICAL |   |      |      |  |
| 52         | Supplying & erecting HMS PVC conduit 40mm dia. with necessary accessories<br>in wall/floor/RCC work/false ceiling/false flooring with chiselling appropriately as per specification no. WG-MA/CC.<br>MR | 1    | Rmt. |  |
| 53         | Supplying & laying flexible HMS PVC conduit 40mm dia. with necessary accessories .<br>MR  | 1    | Rmt. |  |
| 54         | SITC of white Pop-Up box for Library area switch socket installation. The confirguration to consist of 5switch+5 socket complete in all respect, flushed with the table.<br>MR                          | 1    | Nos. |  |

|    |   |   |     |  |
|----|---|---|-----|--|
| 55 | <p>Supply, Installation, testing &amp; commissioning of following light fixtures complete with:</p> <p>a) All fixing accessories, mounting Brackets, anchor fasteners, suspension wires/chains etc. necessary for completeness of installation.</p> <p>b) Drivers / Controllers with housing.</p> <p>c) Lamp of specified wattage.</p> <p>d) Earthing of fittings.</p> <p>e) Diffuser shall lit up uniformly without any black spot on diffuser.</p> <p>f) Light fixture finishes should be as specified.</p> <p>g) Any visible power supply cable to light fixture shall be transparent.</p> <p>h) All suspended fixtures shall be provided with SS caps to put around suspension at false ceiling level</p> <p>Note:</p> <p>1) In addition to above mentioned accessories details, vendor to consider specific light fixture requirement mentioned along-with light fixture.</p> <p>2) Light Fixtures final confirmation to be done by Architect and Lighting Consultant:</p> <p>MR</p> |   |     |  |
|    | 45 W LED DOWN LIGHT FITTING SURFACE MOUNTED / SUSPENSION MOUNTED  | 1 | NOS |  |
|    | 15 W TRACK LIGHT WITH COB LED & EXTRUDED ALUMINIUM HOUSING  | 1 | NOS |  |
|    | SINGLE PHASE 1 MTR. TRACK FOR TRACK LIGHTS  | 1 | SET |  |
|    | LED DECORATIVE HANGING LIGHT FITTINGS   | 1 | NOS |  |
|    | RGB FLOOR STRIP LIGHTS OF 300 mm. LENGTH WITH CONTROLLER  | 1 | NOS |  |
|    | 5 W LED STUDY TABLE LAMP  | 1 | NOS |  |

|    |  |   |     |  |
|----|--|---|-----|--|
| 56 | Supplying and erecting led profile light 12 w conforming IP 65 of any colour with driver complete.<br>Spec. As directed by Engineer-In-Charge.<br>RA   | 1 | RMT |  |
| 57 | Supplying and erecting (OTSL 1251)Track LED fitting 10W/15w with high transitivity<br>diffuser :-Miky/clear PMMA<br>lumen/W, CRI>80, CCT upto3000K/4000k/6000k,<br>Hosing: Die cast Aluminium, IP20,<br>RA     | 1 | NOS |  |
| 58 | Supplying and erecting (OTSL 1252)Track LED fitting 24W/30w/50w with high transitivity<br>diffuser :-Miky/clear PMMA<br>lumen/W, CRI>80, CCT upto3000K/4000k/6000k,<br>Hosing: Die cast Aluminium, IP20,<br>RA | 1 | NOS |  |
| 59 | Supplying and erecting (OSDL 1055)SPOT LED fitting 5W/10w/15w with high transitivity<br>diffuser :-Clear<br>lumen/W, CRI>80, CCT upto 3000K/4000k/6000k,<br>Hosing: Spun Aluminium, IP40,<br>RA                | 1 | NOS |  |
| 60 | Supplying and erecting (OSDL 1057)SPOT LED fitting 20w/30w with high transitivity<br>diffuser :-Clear<br>lumen/W, CRI>80, CCT upto 3000K/4000k/6000k,<br>Hosing: Spun Aluminium, IP40,<br>RA                   | 1 | NOS |  |
| 61 | Supplying and erecting Magnetic Surface Track Channels (size 32mm x 50mm)with available material in Aluminium,Black color,Magnetic Design<br>RA  | 1 | NOS |  |

|          |  |   |      |  |
|----------|--|---|------|--|
| 62       | Supplying and erecting Uplighter Wall lights (OWL 402) Wall lights led:- 18w/ 40w with high transitivity<br>diffuser :-Clear/Frosted Toughened Glass,<br>CCT upto 3000K/4000k/6000k, Hosing: Aluminium, IP65,<br>Durable and Vandal resistant<br>RA  | 1 | NOS  |  |
| 63       | Supplying and erecting (OUL 354)Underwater light fitting 8w/12w/16w with<br>diffuser :-clear/frosted toughened glass , CCT upto3000K/4000k/6000k, Hosing: gun metal/stainless steel, IP68, durable and vandal resistant<br>RA  | 1 | NOS  |  |
|          | FIRE ALARM ACCESSORIES (FF-FAAS) (Addressable)   |   |      |  |
| 64       | Supply, Installation,Testing & Commissioning of Response indicator for all detectors located above false ceiling. Complete as required<br>MR   | 1 | NOS  |  |
| PLUMBING |  |   |      |  |
| 65       | Providing and fixing Stainless steel sink of size 1145 x 510 x250 mm (Graceful Glory - Big ) includng coupling, outlet pipe, elbow and other necessary fitting, finishing etc. complete.<br>RA<br>Spec. As directed by Engineer-In-Charge.   | 1 | NOS  |  |
|          | HVAC   |   |      |  |
| 66       | Supplying, installing and testing of 25 mm thick underdeck insulation. Insulation material shall be Closed Cell Elastomeric Nitrile Rubber. Thermal conductivity of insulation material shall not exceed 0.035 W/(m.K) at mean temperature of 0°C as per EN 12667. Moisture Diffusion Resistance Factor or 'μ' value of insulation material shall be minimum 7,000 without any external barrier as per EN 12086. The insulation shall have fire performance such that it passes Class 1 as per BS476 Part 7 for surface spread of flame as per BS 476 and also pass Fire Propagation requirement as per BS476 Part 6 to meet the Class 'O' Fire category as per 1991 | 1 | Sq.m |  |

|    |   |      |      |  |
|----|---|------|------|--|
|    | Building Regulations (England & Wales) and the Building Standards (Scotland) Regulations 1990 The insulation material shall have fire performance of V0, HB as per UL 94, 1996. Material should be FM (Factory Mutual), USA approved. The insulation material shall be dust and fibre free.<br>MR |      |      |  |
| 67 | Supply, installation, testing and commissioning of Extruded Aluminium Construction powder coated Jet nozzle (201-400 cfm)<br>MR   | 1    | NOS. |  |
| 68 | Supply, installation, testing and commissioning of Extruded Aluminium Construction powder coated Jet nozzle (401-600 cfm)<br>MR   | 1    | NOS. |  |
| 69 | Supply, installation, testing and commissioning of Extruded Aluminium Construction powder coated Jet nozzle (601-800 cfm)<br>MR   | 1    | NOS. |  |
|    | Filteration Unit FOR Small Pond   |      |      |  |
| 71 | Sand Filter<br>800 Filter, Manufactured by simultaneously injecting fiber and resin. Fitted with PVC collectors, diffuser, pressure gauge, manual air bleed and drain valve.<br>1.5" PVC Multiport valve and Initial Charge of Filter Media. Make: Pentair and Equivalent<br>RA                   | 1.00 | NOS  |  |
| 71 | Pump for Pool Filter<br>Type : Basket Strainer<br>Hose Power : 4-6 HP<br>Make : Leo and Equivalent<br>RA  | 1.00 | NOS  |  |
| 71 | Suction Sweeper with Maintenance Kit:<br>Vacuum Head, Floating Hose of 9 Meters Length, 2 x 2.4 M Length Telescopic Handle, Leaf Rake, 18" Wall Brush, pH and Chlorine Test Kit,<br>Make : Emaux and Aarav Enterprises<br>RA  | 1.00 | SET  |  |
| 71 | Drain Cover<br>Make : Emaux   | 1.00 | NOS  |  |

|    |  |      |     |     |
|----|--|------|-----|-----|
|    | RA   |      |     |     |
| 71 | Suction Cover<br>Make : Emaux<br>RA  | 1.00 | NOS |     |
| 71 | Vacuum Nozzle<br>Make : Emaux<br>RA  | 1.00 | NOS |     |
| 71 | Floor Inlet<br>Make : Emaux<br>RA  | 1.00 | NOS |     |
| 71 | Panel Board For LED Lights(Warm Colour)<br>Made from Mild Steel Sheets to house Drivers with controls.<br>Make : Aarav Enterprises<br>RA   | 1.00 | NOS |     |
| 71 | Supplying and erecting Uplighter Wall lights (OWL 406) Wall lights led:- 2X18w/ 2X40w with high transitivity<br>diffuser :-Clear/Frosted Toughened Glass,<br>CCT upto 3000K/4000k/6000k, Hosing: Aluminium, IP65, Durable and Vandal resistant<br>RA | 1.00 | NOS |     |
|    | AUDIO VISUAL SPEAKERS  |      |     |     |
| 72 | Installation Programing Caliberation with excecution<br>Digital Analogue Semi Mixing Console Sound Craft SI Impact/ 32 Input<br>MR   | 1.00 |     | NOS |
| 73 | Installation Programing Caliberation with excecution<br>Instrumental Microphone Shure SM 57<br>MR  | 1.00 |     | NOS |
| 74 | Installation Programing Caliberation with excecution<br>Vocal Microphone Shure SM 58<br>MR   | 1.00 |     | NOS |
| 75 | Installation Programing Caliberation with excecution<br>Wireless Handhel Microphone Shure SVX24IN/PG58<br>MR   | 1.00 |     | NOS |

|    |  |      |  |     |
|----|--|------|--|-----|
| 76 | Installation Programing Caliberation with excecution<br>Wireless Lapel Microophone Shure SVX14/CVL<br>MR | 1.00 |  | NOS |
| 77 | Installation Programing Caliberation with<br>excecution Goose Neck Microphone Shure MX<br>418/C<br>MR    | 1.00 |  | NOS |
| 78 | Installation Programing Caliberation with excecution<br>Hi Net Microphone for Chorus PGA 81<br>MR        | 1.00 |  | NOS |
| 79 | Installation Programing Caliberation with excecution<br>Genreal Purpose Microphone Shure PGA 58<br>MR    | 1.00 |  | NOS |
| 80 | Installation Programing Caliberation with excecution<br>Drumkit Microphone PGDMK -7<br>MR                | 1.00 |  | set |
| 81 | Installation Programing Caliberation with excecution<br>Satge Box<br>MR                                  | 1.00 |  | NOS |
| 82 | Installation Programing Caliberation with excecution<br>Amphenol XLR & RCA Connector<br>MR               | 1.00 |  | set |
| 83 | Installation Programing Caliberation with excecution<br>32 U WQ Exhaust Rack With Shelf & Power<br>MR    | 1.00 |  | NOS |
| 84 | Installation Programing Caliberation with excecution<br>Snake Cables & Connector Percon<br>MR            | 1.00 |  | RMT |

|    |   |      |  |     |
|----|---|------|--|-----|
| 85 | Installation Programing Caliberation with excecution<br>Speaker Cable 2.5 sqmm<br>MR  | 1.00 |  | RMT |
| 86 | Installation Programing Caliberation with excecution<br>Speaker Cable 4.00 Sqmm<br>MR   | 1.00 |  | RMT |
| 87 | Installation Programing Caliberation with excecution<br>Sommer Interconnect Cables<br>MR  | 1.00 |  | set |
| 88 | 2000W active, portable loudspeaker system; 10-inch<br>woofer; 1.0-inch compression driver; 90 degree<br>conical waveguide; dual angle pole socket; presets<br>and user adjustable DSP. For use as main or stage<br>monitor.<br>MR                                 | 1.00 |  | nos |
| 89 | 18" ported, 1500W subwoofer with integrated<br>casters.<br>MR   | 1.00 |  | nos |
| 90 | 2000W active portable loudspeaker system; 12-inch<br>woofer; 1.0-inch compression driver; 75 degree<br>conical waveguide; dual angle pole socket; presets<br>and user adjustable DSP. For use as main or stage<br>monitor. INCLUDES 1x EU CABLE IN CARTON<br>MR   | 1.00 |  | nos |
| 91 | 2000W active, portable loudspeaker system; 12-inch<br>woofer; 1.0-inch compression driver; 105 degree<br>conical waveguide; dual angle pole socket; presets<br>and user adjustable DSP. For use as main or stage<br>monitor. INCLUDES 1x EU CABLE IN CARTON<br>MR | 1.00 |  | nos |

|               |   |      |  |     |
|---------------|---|------|--|-----|
| 92            | Unified Series Core with 24 local I/O channels, 128x128 network I/O channels, dual LAN ports, telephone POTS, 16x16 GPIO, 16 AEC channels, 1RU MR   | 1.00 |  | nos |
| 93            | 4 channels, 2000 watts burst power/ch @ 4Ω, Q-LAN network input from Q-Sys Core MR  | 1.00 |  | nos |
| 94            | 4 channels, 1400 watts burst power/ch @ 4Ω, Q-LAN network input from Q-Sys CoreMR   | 1.00 |  | nos |
| MISCELLANEOUS |   |      |  |     |
| 95            | Aluminium Fins:-<br>Providing and Fixing Horizontal fins with 3"x1" Aluminium Tubular Section Powder coated Horizontally with 1" facing and 3" Gap in to in in sections with 1"1" Aluminium Angle powder coated fixed at top and bottom for fixing, with Hardware , with labour inclusive.<br>MR  | 1    |  | SMT |
| 96            | Providing & fixing AC Charger of model named as AC Type 2 with power rating of 7.4 kW & charging connector IEC62196-2 Gun, the input power supply should be of one phase with all required accessories. (For all 4 W of 2nd generation like Nexon, MG, Mercedes etc.) complete as per specification and drawing provided by the Engineer Incharge<br>RA | 1.00 |  | NOS |
| 97            | Providing & fixing AC Charger of model named as Bharat AC01 with power rating of 3x3.3 KW & charging connector 3 nos. of 16 A Socket, the input power supply should be of three phase with all required accessories. (For 2/3 W & 4 W slow charging) complete as per specification and drawing provided by the Engineer Incharge<br>RA                  | 1.00 |  | NOS |

|     |   |      |  |     |
|-----|---|------|--|-----|
| 98  | Providing & fixing DC Fast Charger of model named as CCS2 with power rating of 30 KW & charging connector 1 nos. of 30 KW CCS2 gun, the input power supply should be of three phase with all required accessories and the output current will be 125 A per Gun. (For all 4 W of 2nd generation like Nexon, MG, Mercedes etc.) complete as per specification and drawing provided by the Engineer Incharge<br>RA   | 1.00 |  | NOS |
|     | Aluminium section False Ceiling   |      |  |     |
| 99  | Providing and fixing Aluminium open cell(100mmx100mm) ceiling 0.45/0.50 mm Galvanized steel and 0.5/0.65mm Aluminium TCT ,Various Gap 50mm to 100mm made of 0.5mm/0.6mm thick black coil coated galvanised steel /powder coated .20mm Wide,40mm deep, 55 microns thick powder coating on exposed surface , 25 microns polyster coil coated over primer on visible surface with primer coat on rear side. Suspension with 4mm dia Galvanized rod ,Height Adjustment Spring STEel big Clip,panel Coupler,GS wall angle. complete as per specification and drawing provided by the Engineer Incharge<br>RA |      |  |     |
|     | 100mmX100mm   | 1.00 |  | SMT |
|     | 150mmX150MM   | 1.00 |  | SMT |
|     |   |      |  |     |
| 100 | Providing and fixing Hands Free Aluminum Foot Door Opener as per drawings and specification provided by the engineer in charge including all fitting complete with Coating complete as per specification and drawing provided by the Engineer Incharge<br>RA  | 1.00 |  | NOS |

|     |  |      |  |     |
|-----|--|------|--|-----|
| 101 | <p>Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade approved face Laminate 1 mm thick on both faces with ghana teak wood frame of size (125mm x 75mm) with malemaine poshlish , Aluminium Louverd of size (0.6 M X 0.3 M) fixed at bottom for ventilation purpose. all included necessary beads, mouldings lipping patti , iron hold fast, SS Hinges , fixer fastening with Cylinder Half lock with handle, SS handles on inside side (vertical - length 300 mm ) and Aluminum Extruded Door Closer fittings etc. completed As per detailed design and drawings. and with all fittings etc. completed. ) complete as per specification and drawing provided by the Engineer Incharge<br/>RA</p> | 1.00 |  | SMT |
|     |  |      |  |     |
| 102 | <p>Supply and Installation of GI DOOR FOR DUCT (0.6 X 1.8MT) AND GLASS (0.3 X 1.00MT) with all the necessary hardware complete as per specification and drawing provided by the Engineer Incharge<br/>RA</p>   | 1.00 |  | NOS |
|     |  |      |  |     |
| 103 | <p>Providing High Density plastic chair(Nilkamal) Smooth and Satin finish with armrest with steel legs size 585mmx550mmx775 mm weight Capacity 125kg ,complete with approved colour ETC(Novella 10)<br/>RA</p>   | 1    |  | NOS |