



मिरा-भाईंदर महानगरपालिका

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईंदर(प)

पाणी पुरवठा व मलनिःसारण विभाग

संकेतस्थळ - www.mbmc.gov.in

ई-मेल - watersupply@mbmc.gov.in

संपर्क - 281922828-251



जा.क्र.मनपा/पापु व मलनि/ ९९४३ /2023-24

दि. १२/१२ /2023

प्रति,

सिस्टम मॅनेजर

संगणक विभाग

मिरा-भाईंदर महानगरपालिका

विषय :- मिरा भाईंदर महानगरपालिका क्षेत्रातील मिरारोड (पूर्व) येथील 15 नंबर बस स्टॉपजवळील मलनिःसारण केंद्र झोन 8 येथील पुर्नःप्रक्रिया केंद्रातील दोषपूर्ण घटकांची दुरुस्ती करणे.

मिरा भाईंदर महानगरपालिका क्षेत्रातील मिरारोड (पूर्व) येथील 15 नंबर बस स्टॉपजवळील मलनिःसारण केंद्र झोन 8 येथील पुर्नःप्रक्रिया केंद्रातील दोषपूर्ण घटकांची दुरुस्ती करणे या कामाची निविदा मागविणेकरीता अंदाजपत्रक तयार करावयाचे आहे. परंतु सदर कामाअंतर्गत खालील नमुद बाबींकरीताचे दर दरसूचीमध्ये उपलब्ध नसल्याने ऑन-लाईन दर मागविणे करीता सोबत जोडलेल्या बाबींचा तक्ता www.mbmc.gov.in या संकेत स्थळावर प्रसिध्द करण्यात यावा.

(शरद नानेगांवकर)

कार्यकारी अभियंता

पाणी पुरवठा व मलनिःसारण विभाग

मिरा-भाईंदर महानगरपालिका



मिरा-भाईदर महानगरपालिका

पाणी पुरवठा व मलनिसारण विभाग

स्व. इंदिरा गांधी भवन, छत्रपती शिवाजी महाराज मार्ग, भाईदर(प)

ता. जि.ठाणे - 401 101



मिरा भाईदर महानगरपालिका क्षेत्रातील मिरारोड (पूर्व) येथील 15 नंबर बस स्टॉपजवळील मलनिःसारण केंद्र झोन 8 येथील पुर्नःप्रक्रिया केंद्रातील दोषपूर्ण घटकांची दुरुस्ती करणे. या कामाची निविदा मागविणेकरीता अंदाजपत्रक तयार करावयाचे आहे. त्याकरीता मिरा-भाईदर महानगरपालिका खालील तक्त्यातील बाबींकरिता ऑनलाईन दर मागवित आहे.

उपरोक्त कामाअंतर्गत बाबींचे दर दि.12/12/2023 ते दि.19/12/2023 रोजी दुपारी 12.00 वाजेपर्यंत watersupply@mbmc.gov.in या ई-मेल वर पाठविण्यात यावे.

Sr. No	DESCRIPTION OF WORK	Qty	Unit	Rate (Excluding GST)
1	REPAIRs TO VALVE ACTUATOR Supply, Installation, Testing & Commissioning including service engineer visit for replacement of Casing Body for Actuator with re-installation of 200 NB Butterfly Auto valve etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	Nos.	
2	CHEMICAL DOSING TANK Supply, Installation, Testing & Commissioning with Test & Trial of Chemical Dosing Tank of 200 litres capacity with required nozzles along with all required hardware & material with re-installation for Dosing pumps etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	3	Nos	
3	CCTV MONITORING SYSTEM Repairs, Rectification, Reconditioning & Re-Commissioning of existing CCTV monitoring system along with replacement of cameras and cables etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	LS	
4	AIR CONDITIONING SYSTEM Repairs, Rectification, Reconditioning & Re-Commissioning of Air Conditioning System at PLC room -3 tons capacity, with required coolant gas etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	Nos	
5	VOLTAGE STABILISER Repairs, Rectification, Reconditioning & Re-Commissioning of Volage Stabiliser for UPS Invertor with all rquired material etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	Nos	
6	CPU WITH LICENSE KEY Supply, Installation, Testing & Commissioning along with service engineer visit for Test & Trial of CPU Dell Make of 16 GB RAM of 502 GB SSI hard disk for replacement Existing crashed CPU of 8 GB RAM of 126 GB normal hard disk. Reinstallation, reconfiguration and commissioning of PLC with License key over desktop of new CPU. etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	LS	

कार्यकारी अभियंता

पाणी पुरवठा व मलनिःसारण विभाग
मिरा-भाईदर महानगरपालिका

जा.क्र.मनपा/पा.पु.व मलनि/

/2023-24

दि.




MIRA-BHAINDAR MUNICIPAL CORPORATION
Water Supply & Sewerage Department
Indira Gandhi Bhavan, Chatrapati Shivaji Maharaj Marg,
Bhayandar (W) 401101, Tal. Dist – Thane, 28192828



Mira Bhaingar Municipal Corporation Want to Float a tender of Replacement/Repair /Rectification of defective components of 5 MLD TTP, STP Zone-8 at Mira Road in MBMC Area. For this Municipal Corporation need online rates of the items mentioned in following chart.

The rates will be Submitted on watersupply@mbmc.gov.in from Dt.12/12/2023 to Dt.19/12/2023 upto 12.00 noon.

Sr. No	DESCRIPTION OF WORK	Qty	Unit	Rate (Excluding GST)
1	REPAIRS TO VALVE ACTUATOR Supply, Installation, Testing & Commissioning including service engineer visit for replacement of Casing Body for Actuator with re-installation of 200 NB Butterfly Auto valve etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	Nos.	
2	CHEMICAL DOSING TANK Supply, Installation, Testing & Commissioning with Test & Trial of Chemical Dosing Tank of 200 litres capacity with required nozzles along with all required hardware & material with re-installation for Dosing pumps etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	3	Nos	
3	CCTV MONITORING SYSTEM Repairs, Rectification, Reconditioning & Re-Commissioning of existing CCTV monitoring system along with replacement of cameras and cables etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	LS	
4	AIR CONDITIONING SYSTEM Repairs, Rectification, Reconditioning & Re-Commissioning of Air Conditioning System at PLC room -3 tons capacity, with required coolant gas etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	Nos	
5	VOLTAGE STABILISER Repairs, Rectification, Reconditioning & Re-Commissioning of Volage Stabiliser for UPS Invertor with all rquired material etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	Nos	
6	CPU WITH LICENSE KEY Supply, Installation, Testing & Commissioning along with service engineer visit for Test & Trial of CPU Dell Make of 16 GB RAM of 502 GB SSI hard disk for replacement Existing crashed CPU of 8 GB RAM of 126 GB normal hard disk. Reinstallation, reconfiguration and commissioning of PLC with License key over desktop of new CPU. etc complete as per detailed specifications and as instructed by Engineer-In-Charge.	1	LS	


Executive Engineer
Water and Sewerage Department
Mira Bhaingar Municipal Corporation

No :- MNP/WS & Sew/ /2023-24
Date :-